

SECTION 00910

ADDENDUM NUMBER 1

DATE: August 13, 2020

PROJECT: Jackson Harbor Breakwater
Chicago, IL

PROJECT NUMBER: 60283337

OWNER: Westrec Marinas
Chicago, ILENGINEER: AECOM
303 East Wacker, Suite 1400
Chicago, IL 60601
312.373.6577

TO: Scott Stevenson

This Addendum forms a part of the Contract Documents and modifies the Bidding Documents dated June 27, 2019, with amendments and additions noted below.

DRAWINGS

Attached are revised drawings dated 8/13/2020. Changes are listed in the table below.

Sheet	Detail or Section	Change
All		Replaced SKZ 20 sheet piling with SKZ 24 sheet piling
S-01	1	Included waler lengths for each cell
S-01	1	Included detail callout bubbles
S-01	A, B	Lowered bottom of concrete by one inch (i.e. increased concrete thickness by one inch)
S-01	Notes	Added requirement for top of CA-7 to be compacted
S-01	Notes	Added the following requirements: <ul style="list-style-type: none"> 1. A layout of construction joints to be submitted for review and approval 2. Contractor shall field verify conditions and notify owner of discrepancies prior to work 3. Contractor shall be aware that filling cell prior to bracing installation (i.e. Sequence Step #3) could cause sheet piling to deflect outwards by approximately 1 inch
S-01	Notes	Changed "Typical Construction Sequence" to "Suggested Construction Sequence"
S-02	2	Made weld "all-around"
S-02	3	Made weld at end of brace "all-around"
S-02	4	Included an extra 1/2" stiffener with all-around weld at end of brace
S-02	3, 6, 7	Included end plates, fill plates, and bolts at ends of walers
S-03	Deck Plan	Deleted references to sawcut joints
S-03	A	Added (2) #5 U-bars at each belly-out
S-03	A	Added note requiring 2" clear between rebar and sheet piling
S-03	A	Modified tining callout and note to state that tining shall be per IDOT
S-03	2	Added (2) #5 U-bars at each belly-out
S-04	1, 2	Added requirement for post to be painted per specifications
S-04	1	Changed anchor embedment depth from 9 to 10 inches
S-04	1, 2	Added requirement for grout to be 8,000 psi @ 28 days
S-04	4	Showed requirement for rebar to be continuous across construction joint

S-04	4	Showed requirement for rebar to be lapped a minimum of 48 bar diameters on one side of construction joint
S-04	5	Deleted detail
S-05	1	Made welds for ladder top handles "all around"
S-05	1	Increased number of rungs from 9 to 10
S-05	3	Made typical weld at ends of rungs "all around"

BID QUANTITIES:

1. The following are revisions to SECTION 00410, Bid Form.
 - A. REMOVE: CA-6 bid item
 - B. REVISE: CA-7 bid item quantity from 3016 tons to 3316 tons


SPECIFICATIONS:

1. The following are revisions to Specification SECTION 05502.
 - A. Revise minimum values for substitution in Paragraph 2.1.2.

Nothing in this Addendum shall be construed as changing other requirements of the Bidding Documents.

END OF ADDENDUM NO. 1

AECOM



By: William Weaver, P.E.