

**WESTREC MARINA MANAGEMENT, INC.
ON BEHALF OF THE CHICAGO PARK DISTRICT**

**INVITATION FOR BID (IFB)
FOR
DELIVERY OF FLOATING DOCKS AT BURNHAM HARBOR**

W-20002

Addendum 2

Q. Is there soil info to determine the pile requirements., or can you supply the pile requirements.

A. Attached please find soil borings, water level information and harbor depths (taken on 10/20/2020).

We prefer a chain anchoring design for piers M, N and O. We prefer as system with 1/2" chain. You can design this to attach with collars to our existing plies with sleeves. The piles could then be cut off 3' above the mud line. The piles are visible on Google Earth.

For piers K and L, we prefer a pile anchoring system. We plan to reuse the existing piles which are generally 14" x 60'-70', with a 3/8"-1/2" wall thickness. We also will require soldier piles between the fingers as part of this design. Your bid should NOT include the piles or chain, but should include pile rings and chain lockers.