

**WESTREC MARINA MANAGEMENT, INC.
ON BEHALF OF THE CHICAGO PARK DISTRICT**

**INVITATION FOR BID (IFB)
FOR
REMOVAL AND MODIFICATION OF DOCK PILES**

W-20004

Addendum 1

Q. Confirm the following quantities:

Removal of dock pilings L: 3, M: 5, N: 4, O: 9

Reuse of dock pilings L: 4, M: 5, N: 6, O: 3

A. No piles are to be removed from Dock L in this phase.

Removal of dock pilings M: 5, N: 4, O: 9

Reuse of dock pilings L: 4, M: 5, N: 6, O: 3

Q. Confirm there is no work associated with the piles marked "Piles Currently Used"

A. "Piles Currently Used" on O dock will have to be cut off 48 inches from the bottom while retaining the current anchor chains for P dock. No changes will be required for "Piles Currently Used" at P dock.

Q. For the "Existing Piles to be Reused", will it be acceptable to cut the pile and attach the collar using divers rather than extract and redrive the pile??

A. Yes.

Q. Confirm docks will be removed by others prior to mobilization or provide anticipated condition.?

A. Yes. Docks have already been removed.